

**PIMPRI CHINCHWAD NEW TOWN DEVELOPMENT AUTHORITY, NEAR AKURDI**  
**RAILWAY STATION, PUNE-44**

Name of work :- Construction of spine Road 75 M wide between Bhakti Shakti and Triveni Nagar. (NH 4 to NH 50)

**E-TENDER NOTICE NO 9 FOR 2013-2014 (Second call)**

Common set of deviation/ clarification based on pre-bid conference held in the office. The Executive Engineer, PCNTDA on 05/09/2013 @ 15:00 hrs to be read with the tender and to be treated as part of the tender.

**COMMON SET OF DEVIATION**

| Sr. No  | Queries Raised by  | Reference                                    | Queries/request raised by Bidders  | Clarifications/correction   |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
|---------|--|--|--|---|---------|-------------|------|----------|----|-----------------------------------|-----|--|-----|------------------------------------|-----|--|------|--|-----|--|
| 1       | M/s.NA Construction Pvt.Ltd. Mumbai  | Para 8-8 ii a (page 7&8)                     | Eligibility of Bidder, it is requested that execution of quantities in respect of Bituminous Bound Macadam is specified as 30% of tender provision quantities. An equivalent executed quantity of DBM/BC etc be accepted as BBM is comparatively less uses item by various Govt./ Semi. Govt Departments.  | <p>ii) To qualify the applicant must have achieved as minimum the following performance during the last three years.</p> <p>a) Total quantities of Road Work with MORTH / STATE PWD specifications of following volume should have been completed during any one of last three years as per form VII</p> <table border="1"> <thead> <tr> <th>Sr. No.</th> <th>Description</th> <th>Unit</th> <th>Quantity</th> </tr> </thead> <tbody> <tr> <td>i)</td> <td>Earthwork (Excavation/Embankment)</td> <td>Cum</td> <td><i>Not less than 30% of this tender quantity</i></td> </tr> <tr> <td>ii)</td> <td>Granular Sub Base/ Wet Mix Macadam</td> <td>Cum</td> <td><i>Not less than 30% of this tender quantity</i></td> </tr> <tr> <td>iii)</td> <td>BBM/OGPC/ Bituminous Macadam/ Dense Bituminous Macadam/Bituminous Concrete</td> <td>Cum</td> <td><i>Not less than 30% of this tender quantity</i></td> </tr> </tbody> </table> | Sr. No. | Description | Unit | Quantity | i) | Earthwork (Excavation/Embankment) | Cum | <i>Not less than 30% of this tender quantity</i> | ii) | Granular Sub Base/ Wet Mix Macadam | Cum | <i>Not less than 30% of this tender quantity</i> | iii) | BBM/OGPC/ Bituminous Macadam/ Dense Bituminous Macadam/Bituminous Concrete | Cum | <i>Not less than 30% of this tender quantity</i> |
| Sr. No. | Description  | Unit   | Quantity   |   |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
| i)      | Earthwork (Excavation/Embankment)  | Cum  | <i>Not less than 30% of this tender quantity</i>   |   |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
| ii)     | Granular Sub Base/ Wet Mix Macadam   | Cum  | <i>Not less than 30% of this tender quantity</i>   |   |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
| iii)    | BBM/OGPC/ Bituminous Macadam/ Dense Bituminous Macadam/Bituminous Concrete | Cum  | <i>Not less than 30% of this tender quantity</i>   |   |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
|         |  | Statement No I on page 79,                   | Regarding (Table showing requirements of ownership of machinery) it is requested to allow the same procured on Hire Purchase basis also alongwith owned Machinery As cost exclusive owned machinery vis a vis estimated cost of work make the project cost practically unviable. (Allowing Machinery on Hire Purchase basis is followed by majority of clients in projects of similar magnitude) | Item No.3-- stone crusher cum screening unit may be hired<br>Item No.11-- Dumper & Tipper total 15 out of which 10 may be hired & 5 on ownership .  |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
|         |  | Sr.No.11 of Page 79                          | Ownership of Transit Mixers may also be considered alongwith Dumper/Tippers  | N.I.T. Prevails   |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
| 2       | M/s.H.C Kataria Pimpri   | Form No VII -Page No 85                      | As per format Certificate from C.A. required certificate from E.E concerned may please be allow.   | N.I.T. Prevails   |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
|         |  | Chapter No 1 Page 5 Point No 4               | EMD and cost of tenders from in from to DD to Nationalise bank   | EMD - D.D. of a bank  |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
|         |  | Schedule B and Specification                 | For concrete items to substantial no.5 concrete mix is proposed 50% Rivers + 50% crushed and as per P. No. 152/ Item 4.1   | N.I.T. Prevails   |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |
|         |  | Item no. 4.5 Bituminous Concrete Page No.124 | Bituminous Concrete Item includes - bitumen binder @ 50% to mix and cement filler.   | <u>Item no. 4.5</u> Providing and laying 40 mm thick Bituminous Concrete(BC) with 40-60 TPH hot mix plant producing an average output of 35 tones / hr using crushed aggregates of specified grading , premixed with bitumen binder @ 6.50% of mix and cement filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification Clause No 509. Spec No. M.O.R.T.& H 509 (60/70 Grade,6.5% Bitumen)   |         |             |      |          |    |                                   |     |  |     |                                    |     |  |      |  |     |  |


|   |                            |   |                 |
|---|----------------------------|---|-----------------|
| 3 | M/s.V.M<br>Matere<br>Moshi | १) वरील संदर्भीय कामामध्ये पूर्ण रस्त्याची जागा ताब्यात आहे का? | N.I.T. Prevails |
|   |                            | २) जागा ताब्यात नसल्यास कधी मिळणार ?                            | N.I.T. Prevails |
|   |                            | ३) कार्यादेश जागा ताब्यात आल्यानंतर देणार, कि आधी देणार?        | N.I.T. Prevails |
|   |                            | ४) चालू देयकाचा धनादेश किती दिवसात मिळणार?                      | N.I.T. Prevails |

**ADDENDUM/CORRIGENDUM FOR CONSTRUCTION OF SPINE ROAD 75 M WIDE BETWEEN BHAKTI SHAKTI AND TRIVENINAGAR, (NH4 TO NH50)**


| SN | ITEM NO | AS PER TENDER DESCRIPTION   | ADDENDUM/CORRIGENDUM   |
|----|---------|---|--|
| 1  | 4.5     | Bituminous Concrete:<br>Providing and laying 40 mm thick Bituminous Concrete(BC) with 40-60 TPH hot mix plant producing an average output of 35 tones / hr using crushed aggregates of specified grading , premixed with bitumen binder @ 50% of mix and cement filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification Clause No 509. Spec No. M.O.R.T.& H 509 (60/70 Grade,6.5% Bitumen) | Bituminous Concrete:<br>Providing and laying 40 mm thick Bituminous Concrete(BC) with 40-60 TPH hot mix plant producing an average output of 35 tones / hr using crushed aggregates of specified grading , premixed with bitumen binder @ 6.5% of mix and cement filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification Clause No 509. Spec No. M.O.R.T.& H 509 (60/70 Grade,6.5% Bitumen) |

Note :- The Revised and corrected clarification for Item no. 4.5 considered as above.

This CSD is to be duly signed and returned in envelope No 1.

  
Chief Executive Officer  
Pimpri Chinchwad New Town  
Development Authority, Nigdi Pune-44

  
Dy. Engr

  
Executive Engineer (A)

  
Superintending Engineer

CAFO